




NOZZLE SCHEDULE													
ITEM	SIZE	RATING	TYPE	MATL	PROJ IN	PROJ OUT	REMARKS						
Α	3/4"	N.P.T.	W.F.	C.S. STD. STD. DRAIN		DRAIN							
В	2"	N.P.T.	W.F.	C.S.	STD.	STD.							
С	3"	N.P.T.	W.F.	C.S.	STD.	STD.	EMERGENCY VENT OPENING						











RIGHT SIDE

NOTES:

- A. Quantity:
- B. Material: H.R. Carbon Steel
- C. Tank: 12 GA w/ 10 GA Top
- D. Design & Operating Pressure: Atmospheric.E. Design & Operating Temperature: Ambient.
- F. Tank to be Built & Labeled per U.L. Spec. #142.
- G. Tank to Bear Manufacturers & U.L. Labels Only.
- H. Tank to be Air Tested with Water & Soap Suds Solution.
- I. Interior: Remove Weld Slag (Ship Clean & Dry). J. Exterior: Gray primer included; see Sales Order for top coat.
- K. All Fittings to be Protected for Shipment.
- L. Customer has the Responsibility to Verify All Dimensions.

APPROVAL FOR CONSTRUCTION
SCHEDULE A - MASTER TERMS &
CONDITIONS OF SALE*

*All pages of this Schedule A are incorporated by reference and are a part of the additional terms of the Master Terms &

Conditions of Sale.

www.newberrytanks.com/masterterms.pdf

☐ APPROVED AS DRAWN.

☐ APPROVED WITH NOTED CHANGES, CONSTRUCTION WILL BE SCHEDULED WHEN SIGNED DRAWING AND CONFIRMED ORDER ARE RECEIVED.

SIGNATURE_ DATE:

SALES ORDER #



860 Johnson Drive Delano, MN 55328 www.fluidall.com

VESSEL DESCRIPTION:

180 GALLON BENCH TOP SINGLE WALLED TANK

CUSTOMER	:	P.O.#	P.O.#							
-										
DATE:	SCALE:	DWG.#	DRAWN BY:	TC						
		SSWBTT180	CHKD. BY:	TB						